TIP NO.	SHEET NO.
R-0513 BB & C	SIGN-3

Pay Item Notes:

1	RELOCATE SIGN, TYPE A (OVERHEAD)
2	RELOCATE SIGN, TYPE B (OVERHEAD)
3	RELOCATE SIGN, TYPE A (GROUND MOUNTED)
4	RELOCATE SIGN, TYPE B (GROUND MOUNTED)
5	RELOCATE SIGN, TYPE D
6	RELOCATE SIGN, TYPE E
7	RELOCATE SIGN, TYPE F
8	RELOCATE SIGN, MILEMARKERS
9	RELOCATE SUPPORT, OVERHEAD SIGN SYSTEM
10	RELOCATE SUPPORT, STEEL BEAM
11	RELOCATE LIGHTING SYSTEM
12	RELOCATE SUPPORT, WOOD
13	STOCKPILE SUPPORT, STEEL BEAM
14	DISPOSAL OF SUPPORT, STEEL BEAM
15	STOCKPILE SUPPORT, WOOD
16	DISPOSAL OF SUPPORT, WOOD
17	STOCKPILE SUPPORT, OVERHEAD STRUCTURE
18	DISPOSAL OF SUPPORT, OVERHEAD STRUCTURE
19	STOCKPILE SIGN SYSTEM, OVERHEAD
20	DISPOSAL OF SIGN SYSTEM, OVERHEAD
21	STOCKPILE SIGN SYSTEM, STEEL BEAM
22	DISPOSAL OF SIGN SYSTEM, STEEL BEAM
23	STOCKPILE SIGN SYSTEM, U-CHANNEL
24	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
25	STOCKPILE SIGN SYSTEM, WOOD
26	DISPOSAL OF SIGN SYSTEM, WOOD
27	STOCKPILE SUPPORT, U-CHANNEL
28	DISPOSAL OF SUPPORT, U-CHANNEL
29	STOCKPILE SIGN, A OR B (OVERHEAD)
30	DISPOSAL OF SIGN, A OR B (OVERHEAD)
31	STOCKPILE SIGN, A OR B (GROUND MOUNTED)
32	DISPOSAL OF SIGN, A OR B (GROUND MOUNTED)
33	STOCKPILE SIGN, D, E OR F
34	DISPOSAL OF SIGN, D, E OR F
35	STOCKPILE SIGN, MILEMARKERS
36	DISPOSAL OF SIGN, MILEMARKERS
37	DISPOSAL OF SIGN, OVERLAY (OVERHEAD)
38	DISPOSAL OF SIGN, OVERLAY (GROUND MOUNTED)
39	STOCKPILE LIGHTING SYSTEM
40	DISPOSAL OF LIGHTING SYSTEM
41	STOCKPILE LIGHTING FIXTURES
42	DISPOSAL OF LIGHTING FIXTURES
43	STOCKPILE WALKWAY
44	DISPOSAL OF WALKWAY
45	SIGN ERECTION, TYPE A (OVERHEAD)
46	SIGN ERECTION, TYPE B (OVERHEAD)
47	SIGN ERECTION, TYPE A (GROUND MOUNTED)
48	SIGN ERECTION, TYPE B (GROUND MOUNTED)
49	SIGN ERECTION, TYPE D, E, AND F
50	SIGN ERECTION, OVERLAY (OVERHEAD)
51	SIGN ERECTION, OVERLAY (GROUND MOUNTED)
52	DISPOSAL OF SIGN SYSTEM ON SPAN WIRE

General Notes:

. SIGNS FURNISHED BY STATE

. ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TW0 U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING OR PAVEMENT MARKINGS. SEE TRAFFIC CONTROL PLANS.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER

. ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.

. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.

. THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE III REFLECTIVE SHEETING.

. THE CONTRACTOR SHALL BE REQUIRED TO SUBMIT TO THE N.C.D.O.T. FOR APPROVAL, DETAIL DRAWINGS OF LUMINAIRE RETRIEVAL SYSTEM MOUNTING ON OHS ASSEMBLY.

. THE CONTRACTOR SHALL USE LUMINAIRE RETRIEVAL SYSTEM ON ALL OVERHEAD STRUCTURES. WALKWAY AND HANDRAIL IS NOT REQUIRED.

. INSTALLATION OF LUMINAIRE RETRIEVAL SYSTEM SHALL ALLOW LUMINAIRE MAINTENANCE FROM THE SHOULDER WITHOUT THE NEED FOR LANE CLOSURE. THE DRIVE HANDLE OF THE LUMINAIRE RETRIEVAL SYSTEM SHALL BE LOCATED A MINIMUM OF 0.92M (3 ') FROM THE RIGHT EDGE OF THE SHOULDER AWAY FROM THE ROADWAY TRAFFIC.

. THE CONTRACTOR SHALL ENSURE THAT COORDINATION IS ESTABLISHED BETWEEN THE OHS ASSEMBLY AND LUMINAIRE RETRIEVAL SYSTEM FABRICATORS SO THAT A FULLY FUNCTIONAL SIGN AND LIGHTING SYSTEM IS INSTALLED. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY OHS ASSEMBLY AND LUMINAIRE RETRIEVAL SYSTEM INCOMPATIBILITIES, OR INSTALLATION OF A LIGHTING SYSTEM NOT FUNCTIONING TO ITS INTENDED PURPOSE.

DO NOT BEGIN FABRICATION FOR TYPES A & B SIGNS MOUNTED ON OVERHEAD STRUCTURES OR STEEL SUPPORTS UNTIL "S" DIMENSIONS HAVE BEEN FIELD VERIFIED.

Project Notes:

A	CONTRACTOR SHALL RETAIN EXISTING SIGN ASSEMBLY
B	SIGNS TO BE RELOCATED BY OTHERS.

PBSJ 1616 EAST MILLBROOK ROAD, SUITE 310
RALEIGH, NORTH CAROLINA 27609
PHONE: (919) 876-6888

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 17586 ENGINEER J. TODD BROOKS

6/3/04

NOTES

03-JUN-2004 16:41
G:\TIP\R-0513BB&C\R513C\Sign\BB-C\NOTES.dgn
jwi2054