



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

October 9, 2009

Addendum No. 1

RE: Contract ID: C202458

WBS# 45226.3.ST1

F.A. # STM-095-3(105)123

Wilson, Nash Counties (I-5137)

I-95 From Joint North of MP 123 To Nash County Line and From
Wilson County Line To The Tar River

October 20, 2009 Letting

To Whom It May Concern:

Reference is made to the sketch maps and proposal form recently furnished to you on this project.

The following revisions have been made to the Sketch Maps:

On Sheet No. 3 the Summary of Quantities has been revised to add a column for Seeding and Mulching.

The following revisions have been made to the proposal:

On Page No. 2 the project special provision entitled "Specialty Items" has been revised. Please void Page No. 2 in your proposal and staple the revised Page No. 2 thereto.

On Page No. 21 the project special provision entitled "Shoulder Construction" has been revised. Please void Page No. 21 in your proposal and staple the revised Page No. 21 thereto.

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128
FAX: 919-250-4119
WEBSITE: WWW.NCDOT.ORG

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B-2
1020 BIRCH RIDGE DRIVE
RALEIGH NC 27610


On Page No. 1 of the item sheets by copy of this addendum the following pay item is hereby added:

<u>Item</u>	<u>Description</u>	<u>Quantity</u>
17-608400000-E- 1660	Seeding and Mulching	5 ACR

The Contractor's bid must include this new pay item. The contract will be prepared accordingly.

The Expedite File has been updated to reflect this revision. Please download the Expedite Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,



R. A. Garris, PE
Contract Officer

RAG/jag
Attachments

cc: Mr. J. G. Nance, PE
Mr. Ron Hancock, PE
Mr. R. E. Greene, PE
Ms. D. M. Barbour, PE
Mr. J. V. Barbour, PE
Mr. Larry Strickland
Ms. Lori Strickland
Project File (2)

Mr. R. E. Davenport, Jr., PE
Ms. Marsha Sample
Ms. Norma Smith
Mr. Ronnie Higgins
Ms. Penny Higgins
Ms. Jaci Kincaid

- 4. For Memorial Day, between the hours of **6:30 a.m.** Friday and **7:00 p.m.** Tuesday.
- 5. For **Independence Day**, between the hours of **6:30 a.m.** the day before Independence Day and **7:00 p.m.** the day after Independence Day.

If **Independence Day** is on a Friday, Saturday, Sunday or Monday, then between the hours of **6:30 a.m.** the Thursday before Independence Day and **7:00 p.m.** the Tuesday after Independence Day.

- 6. For **Labor Day**, between the hours of **6:30 a.m.** Friday and **7:00 p.m.** Tuesday.
- 7. For **Thanksgiving Day**, between the hours of **6:30 a.m.** Tuesday and **7:00 p.m.** Monday.
- 8. For **Christmas**, between the hours of **6:30 a.m.** the Friday before the week of Christmas Day and **7:00 p.m.** the following Tuesday after the week of Christmas.

Holidays and holiday weekends shall include New Year's, Easter, Memorial Day, Independence Day, Labor Day, Thanksgiving, and Christmas. The Contractor shall schedule his work so that lane closures will not be required during these periods, unless otherwise directed by the Engineer.

The time of availability for this intermediate contract work shall be the time the Contractor begins to install all traffic control devices for lane closures according to the time restrictions listed herein.

The completion time for this intermediate contract work shall be the time the Contractor is required to complete the removal of all traffic control devices for lane closures according to the time restrictions stated above and place traffic in **the existing traffic pattern**.

The liquidated damages are **Ten Thousand Dollars (\$10,000.00)** per hour.

MAJOR CONTRACT ITEMS:

(2-19-02)

RG 28

The following listed items are the major contract items for this contract (See Articles 101 and 104-5 of the *2006 Standard Specifications*):

Line #	Description
4	Asphalt Concrete Surface Course, Type S9.5C

SPECIALTY ITEMS:

(7-1-95)

RG 37

Items listed below will be the specialty items for this contract (See Article 108-6 of the *2006 Standard Specifications*).

Line #	Description
13 thru 15	Long-Life Pavement Markings
16	Permanent Pavement Markers
17	Erosion Control

PROJECT SPECIAL PROVISIONS

ROADWAY

SHOULDER CONSTRUCTION:

(12-21-99) (Rev.7-18-06)

R1 R04 Rev.

Description

The work covered by this provision consists of performing shoulder construction in accordance with Section 560 of the 2006 Standard Specifications and the details of this provision. Construction of a new shoulder is required due to **resurfacing** on the existing roadway. Place earth material along the completed edge of pavement and construct shoulders as shown on the sketch map and/or as directed by the Engineer. Backfill and compact the area to the satisfaction of the Engineer. **Perform this work immediately after the resurfacing operations are completed as directed by the Engineer.**

Materials

Furnish earth material necessary for the construction of the shoulders. Provide earth material meeting the approval of the Engineer. No testing will be necessary.

Measurement and Payment

Shoulder Construction will be measured and paid for as the actual number of shoulder miles that have been constructed. Measurement will be made along the surface of each shoulder and to the nearest 0.01 of a mile. Such price and payment will be full compensation for furnishing earth material, hauling, placing, compaction, and all incidentals necessary to complete construction of the shoulders. **Seeding and Mulching will be paid for as provided elsewhere in this contract.**

Payment will be made under:

Pay Item	Pay Unit
Shoulder Construction	Shoulder Mile

ASPHALT PAVEMENTS - SUPERPAVE:

(7-18-06)(Rev 10-20-09)

RR6R01

Revise the *2006 Standard Specifications* as follows:

Page 6-2, Article 600-9 Measurement and Payment, delete the second paragraph.

Page 6-12, Subarticle 609-5(C)2, Required Sampling and Testing Frequencies, first partial paragraph at the top of the page, delete last sentence and add the following:

If the Engineer allows the mix to remain in place, payment will be made in accordance with Article 105-3.