



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

May 13, 2013

Addendum No. 2

RE: Contract ID C203332

WBS # 34416.3.3, 34416.3.4

State Funded

Cumberland, Sampson Counties (R-2303 A & B) (Proposal No. 3 Cluster)

NC-24 From West Of SR-1006 (Maxwell Road/Clinton Road) To

SR-1404 (Dowdy Road) In Sampson County

May 21, 2013 Letting

To Whom It May Concern:

Reference is made to the proposal form furnished to you on this project.

On Page Nos. 32 thru 36 the list of building removal items has been revised within the project special provision entitled "Building Removal". Please void Page Nos. 32 thru 36 in your proposal and staple the revised Page Nos. 32 thru 36 thereto.

Sincerely,

R. A. Garris, PE
Contract Officer

RAG/jag

Attachments

cc: Mr. Ron Hancock, PE
Mr. Greg Burns, PE
Ms. Karen Fussell, PE
Ms. D. M. Barbour, PE
Mr. J. V. Barbour, PE
Mr. R.E. Davenport, PE
Ms. Lori Strickland
Project File (2)

Mr. Ray Arnold, PE
Ms. Natalie Roskam, PE
Ms. Penny Higgins
Ms. Jaci Kincaid
Mr. Ronnie Higgins
Mr. Larry Strickland
Ms. Marsha Sample

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-707-6900
FAX: 919-250-4119
WEBSITE: www.NCDOT.GOV

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B-2
1020 BIRCH RIDGE DRIVE
RALEIGH NC 27610

PROJECT SPECIAL PROVISIONS

ROADWAY

CLEARING AND GRUBBING - METHOD III:

(4-6-06) (Rev. 1-17-12)

200

SP2 R02B

Perform clearing on this project to the limits established by Method "III" shown on Standard Drawing No. 200.03 of the *2012 Roadway Standard Drawings*.

BURNING RESTRICTIONS:

(7-1-95)

200, 210, 215

SP2 R05

Open burning is not permitted on any portion of the right-of-way limits established for this project. Do not burn the clearing, grubbing or demolition debris designated for disposal and generated from the project at locations within the project limits, off the project limits or at any waste or borrow sites in this county. Dispose of the clearing, grubbing and demolition debris by means other than burning, according to state or local rules and regulations.

BUILDING REMOVAL:

(1-1-02) (Rev. 4-16-13)

215

SP2 R15 C

Remove the buildings, underground storage tanks and appurtenances listed below in accordance with Section 215 of the *2012 Standard Specifications*:

For Project R-2303A:

Building Removal

**Parcel 907 – Left of Approximate Survey Station 171+20, Survey Line L
1 Shed Inside Right of Way**

Building Removal

**Parcel 907 – Left of Approximate Survey Station 171+60, Survey Line L
1 Business Inside Right of Way**

Building Removal

**Parcel 057 – Left of Approximate Survey Station 183+30, Survey Line L
1 SFD Inside Right of Way**

Building Removal

**Parcel 077 – Right of Approximate Survey Station 201+70, Survey Line L
1 Shed Inside Right of Way**

Building Removal

**Parcel 091 – Left of Approximate Survey Station 255+40, Survey Line L
1 Mobile Home Inside Right of Way**

Building Removal

**Parcel 091 – Right of Approximate Survey Station 255+90, Survey Line L
1 Shed/Pool Inside Right of Way**

Building Removal

**Parcel 091 – Right of Approximate Survey Station 256+80, Survey Line L
1 SFD Inside Right of Way**

Building Removal

**Parcel 094 – Right of Approximate Survey Station 258+00, Survey Line L
1 Mobile Home Inside Right of Way**

Building Removal

**Parcel 094 – Right of Approximate Survey Station 259+00, Survey Line L
1 SFD Inside Right of Way**

Building Removal

**Parcel 094 – Right and Left of Approximate Survey Station 259+40, Survey Line L
1 Detached Garage Inside Right of Way**

Building Removal

**Parcel 117 – Left of Approximate Survey Station 324+40, Survey Line L
1 SFD Partially Inside/Outside Right of Way**

Building Removal

**Parcel 129 – Left of Approximate Survey Station 334+80, Survey Line L
1 Mobile Home Inside Right of Way**

Building Removal

**Parcel 133 – Left of Approximate Survey Station 337+50, Survey Line L
1 SFD Partially Inside/Outside Right of Way**

Building Removal

**Parcel 140 – Left of Approximate Survey Station 348+00, Survey Line L
1 Business Partially Inside/Outside Right of Way**

Building Removal

**Parcel 159 – Left of Approximate Survey Station 359+20, Survey Line L
1 Mobile Home Inside Right of Way**

Building Removal

**Parcel 159 – Left of Approximate Survey Station 360+00, Survey Line L
1 SFD Partially Inside/Outside Right of Way**

Building Removal

**Parcel 166 – Left of Approximate Survey Station 372+60, Survey Line L
1 SFD Partially Inside/Outside Right of Way**

Building Removal

**Parcel 168 – Right/Left of Approximate Survey Station 375+00, Survey Line L
1 Business Inside Right of Way**

For Project R2303B:

Building Removal

Parcel 431

Mobile Home

When the description of the work for an item indicates a building partially inside and partially outside the right of way and/or construction area, but does not require the building to be cut off, the entire building shall be removed.

TEMPORARY DETOURS:

(7-1-95) (Rev. 4-15-08)

1101

SP2 R30 A

Construct temporary detours required on this project in accordance with the typical sections in the plans or as directed.

After the detours have served their purpose, remove the portions deemed unsuitable for use as a permanent part of the project as directed by the Engineer. Salvage and stockpile the aggregate base course removed from the detours at locations within the right of way, as directed by the Engineer, for removal by State Forces. Place pavement and earth material removed from the detour in embankments or dispose of in waste areas furnished by the Contractor.